



## Thiruvananthapuram Regional Co-operative Milk Producer's Union Limited

Head Office, Ksheera Bhavan, Pattom, Thiruvananthapuram -  
695004.

Ph:0471-2447109, 2446845 Fax: 2449567 E mail:  
trcmpu@gmail.com

120/TRU/PC/ I/35465/2026

10-10-2026

### **TENDER NOTICE**

Sealed competitive tenders are invited from reputed firms/contractors having sufficient previous experience for executing **Aluminium Fabrication work for File storage room (HRD) at TRCMPU Head office.** All the works should be completed within the time period of **10 days** from the successful receipt of work order.

### **INDEX**

- \* Annexure I – Terms & Conditions
- \* Annexure II – Tender Form
- \* Annexure III – BOQ

|                                    |                              |
|------------------------------------|------------------------------|
| Tender Publishing                  | : 10.10.2026 4.30 PM         |
| Pre Bid Meeting                    | : 13.10.2026 10.30 AM        |
| Last date for submission of tender | : 19.10.2026 2.30 PM         |
| Tender opening                     | : 19.10.2026 3.30 PM         |
| Tender opening place               | : Milma, TRCMPU Head Office. |

### Technical specification

| Sl No    | Type of spec                | Level of Details                                                                |
|----------|-----------------------------|---------------------------------------------------------------------------------|
| <b>A</b> | <b>Aluminium Partitions</b> |                                                                                 |
| 1.       | Fixed Area                  | 240 Sq Ft                                                                       |
| 2        | Aluminium Components        | Powder coated in custom colours on request                                      |
| 3        | Casing                      | 2½ x 1½"                                                                        |
| 4        | Bottom Rail                 | 4½" x 1¾"                                                                       |
| 5        | Top Rail                    | 2½ x 1½"                                                                        |
| 6        | L Bracket                   | MOC Iron with Zinc plated finish                                                |
| 7        | Screws                      | MOC: Caron steel with Zinc plated                                               |
| <b>B</b> | <b>Glass</b>                |                                                                                 |
| 1        | Type                        | Normal                                                                          |
| 2        | Thickness                   | 5mm                                                                             |
| 3        | Make                        | Saint Gobain/reputed make                                                       |
| <b>C</b> | <b>Hylam Sheet</b>          |                                                                                 |
| 1.       | Type                        | High Pressure Decorative Laminate                                               |
| 2.       | Thickness                   | 3.5 mm                                                                          |
| 3.       | Finish                      | Satin                                                                           |
| 4.       | Properties                  | Resistant to normal moisture, heat, stains, impact and every day wear and tear. |
| <b>D</b> | <b>Sliding Door</b>         |                                                                                 |
| 1.1      | Area                        | 7' x 3' = 21 Sq Ft                                                              |
| 1.2      | Aluminium Components        | Powder coated in custom colours on request                                      |
| 1.3      | Casing                      | 2½ x 1½"                                                                        |
| 1.4      | Bottom Rail                 | 4½" x 1¾"                                                                       |
| 1.5      | Top Rail                    | 2½ x 1½"                                                                        |
| 1.6      | L Bracket                   | MOC Iron with Zinc plated finish                                                |

|          |                                         |                                               |
|----------|-----------------------------------------|-----------------------------------------------|
| 1.7      | Screws                                  | MOC: Caron steel with Zinc plated             |
| <b>E</b> | <b>Cement Board Grid Sealing</b>        |                                               |
| 1.01     | Total Area                              | 80 Sq Ft                                      |
| 1.02     | <b>Cement Tile</b>                      |                                               |
| 1.03     | Tile type                               | Laminated Cement Board                        |
| 1.04     | Thickness                               | 6 mm                                          |
| 1.05     | Brand                                   | Gyproc/Armstrong/Shera/USG Boral/Reputed make |
| 1.06     | Size                                    | 600 x 600 mm                                  |
| 1.07     | Fabrication                             |                                               |
| 1.08     | Explosive Bolt                          | 10mm GI anchor bolt                           |
| 1.09     | Hanging Pole                            | GI L angle 1" x ¼"                            |
| 1.1      | Hanging Pole thickness                  | 0.45 mm                                       |
| 1.2      | Hanging Pole Spacing                    | 1.2 meter gap                                 |
| 1.3      | Brand                                   | Ramco/Armserom                                |
| <b>F</b> | <b>Wall Support (Perimeter channel)</b> |                                               |
| 1.       | Type                                    | GI L section                                  |
| 2.       | Thickness                               | 0.45mm                                        |
| 3.       | Mounting                                | Cement screw (6mm)                            |
| 4.       | Size                                    | 1" x 1"                                       |
| 5.       | Screw spacing                           | 1'                                            |
| 6.       | Brand                                   | Gyproc/Armstrong/Shera/USG Boral              |
| <b>G</b> | <b>Main Keel</b>                        |                                               |
| 1.       | Type                                    | GI T angle 1" x 1 ¼"                          |
| 2.       | Spacing                                 | 120cm                                         |
| <b>H</b> | <b>Cross Keel</b>                       |                                               |

|    |               |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |
|----|---------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| 1. | Type          | GI T angle 1" x 1 ¼"                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |
| 2. | Spacing       | 4'                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |
| 3. | Fixing        | 4' and 2'                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |
| 4. | Scope of Work | Providing and fixing Concealed Grid suspended ceiling system of 2' square Cement Boards fixed to Frame Work Metal System concealed grid key lock suspended ceiling system consisting of GI suspension rod, top cross rail of 3000mm long of 0.55BMT and furring channel 4000mm long made of 0.5mm BMT the top cross rail to be suspended from ceiling at every 1200mm and furring channel to be fixed to top cross rail at every 600mm to make a grid of 600 x 600m. All the above components are to be made of galvanized steel. The rates to include cutouts for lighting fixtures, Ceiling fans, etc., along with necessary strengthening and supports for fixing of these. |

—

## **ANNEXURE I**

### **Terms and Conditions**

1. **Tender Submission.** The offer in attached Tender form should be submitted in sealed envelope to the below Address with the quotation No. and due date super scribed on it. The offer should reach the office in the following address on or before 19.10.2026 **02.30 AM** on the due date of submission and shall be opened on prescribed date and time.

The Asst Manager (Projects)  
TRCMPU Ltd, Milma,  
Ksheera Bhavan, Pattom,  
Thiruvananthapuram – 695 004

2. **Price Basis.** The **unit rate** shall be inclusive of the cost of all materials, transportation, labour charges, incidental expenses, taxes and duties, excluding GST, required for the complete execution of the work in all respects. No additional payment shall be made on this account. The rates quoted shall remain firm and unchanged from the date of commencement of the work until its completion in all respects, and no enhancement of rates shall be entertained. **Payment shall be made based on the actual area measured and verified at site, at the approved rates quoted in the tender.**

3. **Validity.** The offer should remain valid for acceptance for a period of **30 days** from the date of opening.

4. **Completion.** The above work should be completed in all respect within **10 days** from the date of receipt of the work order.

5. **Payment.** **60%** of payment shall be released on satisfactory supply and balance on completion of the work and on the basis of quantity/Volume/Masurement. The bill for the work shall be prepared in the name of

The Managing Director  
TRCMPU Ltd, Milma,  
Ksheera Bhavan, Pattom,  
Thiruvananthapuram – 695 004

6. **General**

- The TRCMPU does not bind itself to accept the lowest offer and reserves the right to accept any offer/offers in part or full without assigning any reason.

- The TRCMPU reserves the right to negotiate with bidder / bidders and also the right to reject any or all the offers without giving any reason.
- The TRCMPU shall not be liable for any damage or compensation, in consequence to any accident or injury to any workman or other persons employed by the contractor.
- The work has to be carried out without affecting the day to day operation of the Dairy.
- Damage should not occur to the Electrical Installation, pipe lines, equipment, machinery, etc. while carrying out the work.
- Work will be carried out as per the Terms and conditions and Technical Specifications issued by TRCMPU Ltd.
- The site must be neat and clean after the work.

**WILSON M J**  
**MANAGING DIRECTOR(MDO-THO)**

**ANNEXURE II****Tender Form****(To be filled by the Bidder)**

Tender No. 120/TRU/PC/ I/35465/2026 dated 10-10-2026

Tender Name: Tender for Aluminium Fabrication work for File storage room (HRD) at TRCMPU Head office

Your Ref No.: .....

DATE:

.....

**TENDER FORM**

NAME :

ADDRESS :

CONTACT NO :

E-MAIL-ID :

PREVIOUS EXPERIENCE DETAILS :

(Copy should be submitted )

(Note: Last date for submission – .....)

*signature of Bidder*

—

-  
-  
**ANNEXURE III**  
**(To be filled by the Bidder)**

Tender No. 120/TRU/PC/ I/35465/2026 dated 10-10-2026

Tender Name: Tender for Aluminium Fabrication work for File storage room at TRCMPU Head office

-  
**BOQ**

| SI No | Description        | Qty       | Rate | Amount |
|-------|--------------------|-----------|------|--------|
| 1     | Fixed Area         | 240 Sq Ft |      |        |
| 2     | Door Area          | 21 Sq Ft  |      |        |
| 3     | False Ceiling Area | 80 Sq Ft  |      |        |
|       |                    |           |      |        |

**Total**

**(The rate quoted should be All inclusive except GST)**

We hereby declare that all the details entered by me is correct and I will obey the terms and conditions of the tender No. 120/TRU/PC/ I/35465/2026dated 10-10-2026

*signature of Bidder*

